Project: Construction of Arch and Providing Interlocking Tiles in Front of Sri Baba Temple And Construction of RCC Roof for Ramp Near Ganesha Temple in Work No.57 & Retaining and Improvements to Road from NH-
Circle to Mattikere Fly Over

| Sl.No. | Item of Work | Unit | Approximate Quantity | Rate | Amount in Rs. | Whether the items are alternative to items in the tender or whether they are additional items (If items are in lieu of some items in the accepted tender, such items should be mentioned | Whether the extra items is included in the sanctioned estimate | How the extra cost of the item is proposed to be met | Whether the extra item is included in the schedule of rate of the Division. If so reference to this item of the schedule to be given. If not data sheets should accompany the rate list | Remarks |
|---|---|---|---|---|---|---|---|---|---|---|
| 1 | 2 | | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 1 | KSRB 12-1: Providing and laying in position to required level or slope of internal diameter salt glazed stoneware pipes grade A and jointing with stiff mixture of cement mortar in proportion of 1:1, testing of pipes and joints,including cost of materials, labour charges complete as per specifications. Specification No. KBS 12.2.5/12.7 KSRB 12-1.9 : - d o - 230 mmn I.No 11.4 | Rmt | 331.00 | 584.67 | 193525.37 | Additional item | No | In the revised estimate to be sanctioned later | | |
| 2 | KSRB 12-3 : Providing and laying in position plain cement concrete of mix M 7.5 using 40mm and down size graded granite / trap metal for haunching of internal diameter stoneware pipes, concrete machine mixed laid in layers not exceeding 15 cms thick, well compacted, including cost of materials, labour charges, form work, HOM curing complete as per specifications Specification No. KBS 4.1 / 4.2 I.No 11.22 P.No 73 230 mm | Rmt | 331.00 | 855.19 | 283066.96 | Additional item | No | In the revised estimate to be sanctioned later | | |
| | Total | | | | 476592.00 | | | | | |

"Here by EIRL amount Rs: 4,76,592/- (Rupees four lakhs seventy six thousand five hundred and ninety two only) is approved"

EE
EIRL